


STUART BOUNDARY
PROPERTY
FOR
KENNETH STUART

SECTION BREAKDOWN


SHEET _____

1 OF 5
PROJECT NO. 4457




NOTES:

1. ALL $\frac{3}{8}$ " REBAR SET ARE 24" LONG WITH YELLOW PLASTIC CAP STAMPED "BLEDSO TAPP PC50920004" (BT REBAR)
2. THE PURPOSE OF THIS SHEET IS TO INDICATE SECTION CORNERS AND THE RESPECTIVE POSITIONS RELATIVE TO ONE ANOTHER. IT ALSO INDICATES THE LOCATION OF THE SUBJECT PARCEL (S) RELATIVE TO MOVE.



Sec 9 9N 1W



Bledsoe Tapp & Riggert, Inc.
 Quality Land Surveying and Civil Engineering Services
 1311 West Tapp Road
 Indianapolis, IN 46201
 (317) 336-5877
 FAX (317) 336-0817

**STUART BOUNDARY
 PROPERTY**
 FOR
KENNETH STUART

DESIGNED BY: B.S.
 DRAWN BY: B.S.
 CHECKED BY: B.S.
 DATE: NOVEMBER 11, 2003

SECTION BREAKDOWN

1 OF 5
 PROJECT NO. 4457

Handwritten notes and signatures at the bottom of the page:

- Start 0311 SAB 73 0512 5AD - 71 CTS 2-1-06
- 120-04 Mary Oyle 95 acres 014-17 630-00 012-10580-00
- Handwritten signature: Hama

Nov 15th 1839

Layed off in compliance with an order of the Monroe County Probate Court a mill lot & Dover for the benefit of Sally Williams widow of Zachariah Williams Dec^d & for the benefit of the heirs of said decedent situate in the Sth quarter of section no 32 Town 9 R 1 west & Bounded as follows to wit Beginning at the South west corner of section no 32 witness Live Birch 12 inch diam S 67° W 29 ch distant Birch 15 inch diam N 44½° E 93½ links dist then N 6° W 28 poles to a stone witness Live W Oak 18 inch diameter S 50° W 21 chs dist Birch 20 inch diam S 56½° E 46 chs distant then N 85° E 100 poles to a stone witness Birch 20 inch diam S 18° W 82 chs dist Birch 15 in diam S 72° W 67 chs dist then S 6° E 28 poles to a stone witness poplar 14 inch diam N 74½° E 91½ chs dist then S 88½° E W 100 poles to the Beginning containing 17½ acres

Dover lot Beginning at the Nth Eth cor of Mill lot witness W Oak 18 inch diam S 50° W 21 chs dist Birch 20 inch diam S 56½° E 46 chs distant then N 85° E 70 poles to a stone witness Birch 14 inch diam N 76° W 28 chs dist then N 6° W 133 poles to a stone standing in George W Gardins line witness Birch 10 inch diam S 82° W 37 chs dist W Oak 15 inches diam S 56° W 72 chs dist then S 85° W 71 poles & 5 links to a stone witness W Oak 20 in diam S 82½° W 30 links dist W Oak 15 inch diam S 39° E 43 chs dist then S 6° E 132 poles 7 links to the Beginning containing 58 acres 2 quarters 3 4. Poles 58 2.04

James W. Spencer & Eli D. Harmer
Chas. W. Brown

James W. Spencer M 6 B

Oct 3rd 1839

ran the following designated line in section 7 T 9 R 1 west for John S. Barnes & James Rawlings Began at the E ½ m Post then S 85° W 317 poles & links to the West ½ mile Post then Began at the S ½ m post then N 6° W 330 poles to the Northern ½ mile post witness at the center Birch 12 in diam N 77½° E 44½ chs dist Birch 30 inches diameter N 57° E 36 chs dist

length of the line South of the center 157 poles 4 links
length of the line North of the center 172 poles 21 links
length of the line West of the center 160. poles 18 links
length " East of " center 158 poles 15 links

names of chain bearers /
Not blazed


James W. Spencer M 6 B

Oct 2^d A D 1849

Layed off 2 acres for a mill lot for Nicholas Fierro
 & Daniel Thomas at Bear Blossom Bridge on the Morgantown
 road in Section 35 T⁴ R 1. East Fixed for a starting point
 the N E cor having for witness trees a Sycamore 8 inches
 diameter S 27° E 2 chain & 38 links dist Elm 16 inch diam
 S 22° W 1 chain & 46 links distant ran from said corner
 S 41° W 20 poles then N 41° W 16 poles then N 41° E 20 poles
 then to the starting point

variation 6° degrees

James Woodburn M. C. S.

Feb 16th 1850

Surveyed for James Small the following tract of land in
 Section 15 T⁴ R 2 west in the Nth q^{tr} of said Section
 Beginning at (A) the S E cor of said q^{tr} running North
 106 poles to (B) From (D) the Sth cor of said q^{tr}
 N 106 poles to (C) then from C to B across said q^{tr}
 Established corners at C & B

Witness trees at C Sugar 15 inch diam
 N 36° W 10 1/2 links distant Birch 18 inch diam N 42° E
 43 links dist

at B Black Oak 3 inch diam S 25° W
 23 links distant Hickory 18 inch diam N 38° W 60 1/2 links dist

James Small & Hugh Sample
 chain Bearers

James Woodburn, M. C. S.

March 2^d 1850

Surveyed as Dower to Mary W. Hughes & her husband
 James Hughes thirteen & 5/6 acres in the Nth corner of
 of the Sth q^{tr} of Nth q^{tr} of Section 9 T⁴ R 1. west
 Established the Nth & N E cor with as trees of the Nth
 cor Birch 12 inch diam N 18° W 5 links dist " 16 inch diam
 S 25° E 32 links dist N E cor Birch 12 inch diam S 47 1/2° E
 9 links dist Poplar 8 inch diam N 87° W 20 links dist
 Said Dower was layed off in a Square each side being 47.04
 Poles Variation 5°

John James D. Robertson &
 Joseph Bangh chain Bearers Sworn

James Woodburn M. C. S.

thence S 85° W 79 poles & 1 lb to R witness Beach 15 inches in diam
 N 55° W 12 lbs dist Beach 18 inches in diam S 15° W 15 lbs dist thence S 85° W
 39 poles 15 lbs to S witness R Oak 5 inches in diam S 85° W 7 lbs dist
 R Oak 5 inches in diam N 50° E 21 lbs dist then commenced at the
 N E corner Ran S 85° W 79 poles & 12 lbs to T witness Beach
 15 inches in diam S 87° W 28 lbs dist Beach 18 inches in diam East 3/4 lb
 Chas. Bares I W. Parkham John Logan & William Robertson sworn

John Logan \$1.50 paid
 for Samuel Gitty 3.50 paid J. S. Buskirk, M. C. S.
 Samuel Rand 1.50 paid
 Alexander Robertson 1.50 paid
 William Robertson 1.00 paid
 David Hunter 1.00 paid
 Sarah Romans 1.00 paid
 John Mosure 1.00 paid
 James Flash 1.00 paid

May the 15th 1861

Ran the following lines & made the following corners in
 Section 9, T. 9, R. 1 W. for John Stuffle commenced
 at the N E corner old witness gone new ones made
 Beach 8 inches in diam N 70° W 8 lbs dist

To 10 ... S 15° W 25 ...
 thence S 5° E 100 poles & 7 lbs to the Eastern 1/2 mile post
 thence S 85° W 160 poles & 12 lbs to the center of said Section
 witness Black Berry 10 inches in diam N 35° W 63 lbs dist
 Mul Berry 8 ... S 67° E 90 ...

Chas. Bares } John Stuffle } sworn
 Jacob Stuffle }
 fee \$3.00 paid

J. S. Buskirk M. C. S.

State of Indiana
 County of Monroe J. S. D.

Monroe Common Pleas Court We the Commissioners
 Appointed by said Court at April Term 1861 to make
 Partition of the Real Estate of belonging to Lawson
 Oliphant and Others Heirs of Thomas Oliphant Gent late
 of said County and State Dec. after being duly sworn as
 will appear by an Oath administered on the Warrant of Partition
 delivered to us and here with returned and filed we


T09N-R01W-09_0000_MCS

Ray Graham : PB 314

Feb 20, 1988

23.47 acres.

**BUEHLER ADDITION AMENDMENT TWO
PRELIMINARY PLAT**



4.26
1.12

5.38

SETBACK TABLE		
ZONING R-1		
FRONT YARD	SIDE YARD	REAR YARD SETBACK
70' FROM CENTERLINE	20' + 4' FOR EACH ADDITIONAL STORY	30'


DESIGN PROFESSIONALS

STYNUM FANTO & ASSOCIATES, INC.
528 N. WALNUT ST.
BLOOMINGTON, INDIANA 47404
(317) 332-8010
JEFFREY S. FANTO, P.E.
DOUGLAS R. CURRY, R.L.S. 890005

SUBDIVIDER

ERIC BUEHLER
5185 E. PIERCE ROAD
BENTLEY, IN 47960
(317) 583-0042

EXHIBIT 1: PRELIMINARY PLAT



BYNUM FANYO & ASSOCIATES, INC.

ARCHITECTURE
CIVIL ENGINEERING
PLANNING

May 2, 2007

Monroe County Plan Commission
Courthouse
Bloomington, IN 47404

Re: Buehler Addition Amendment Two formerly JB Minor Subdivision

Commission:

This 2-lot subdivision was originally submitted as a Minor Subdivision. Upon its review, the Planning Staff decided that this subdivision should follow the Major Subdivision procedure. Therefore, our customer, Eric Buehler, is requesting permission to create a 2 - lot Major Subdivision on 5.79 acres on East Whisnand Road. The address is 1680 E. Whisnand Road, Bloomington, Indiana 47408. The name of the subdivision will be Buehler Addition Amendment Two. The subdivision will have one access point. The point is on E. Whisnand Road. The minimum lot size is 1.12 acres.

Mr. Buehler's address and phone number are as follows: 5986 E. Pierce Road, Monticello, IN 47960; 574-583-0042.

The subdivision is in Section 15, Township 9 North, Range 1 West, Bloomington Township, Monroe County, Indiana. It is a part of Tract II in Buehler Addition and the Parcel ID # is 012-03570-00.

This subdivision exists within 1-mile of Marlin School and according to 856-40 (A)(5) a sidewalk is required. With this submittal a waiver for this requirement is being requested. This waiver is being requested because this project does not connect to an existing subdivision or business that has sidewalks, it is not in a business or industrial overlay district, and there are not any sidewalks in the area.

The preliminary plat we are submitting today complies with Chapter 856 to the best of our knowledge. Any omissions or gaps to complying with Chapter 856 are an accidental oversight.



Sincerely,

xc: 5007038

528 NORTH WALNUT STREET
812-332-8030


BLOOMINGTON, INDIANA 47404
FAX 812-339-2990

EXHIBIT 2: PETITIONER'S STATEMENT



DESCRIPTION:

A part of the Southeast quarter of the Southwest quarter in Section 9, Township 9 North, Range 1 West, Monroe County, Indiana, bounded and described as follows; Beginning at the Southeast corner of said quarter and in the centerline of Whisnand Road, thence with the South line of said quarter and leaving said road centerline West for 900.25 feet, thence North 00 degrees 32 minutes West for 456.00 feet, thence North 73 degrees 31 minutes East for 939.00 feet, thence South 60 degrees 25 minutes 19 seconds East for 722.42 feet and to the point of beginning. Containing in all 12.18 acres, more or less. Subject to a 25.00 foot easement from the centerline of Whisnand Road for County Highway right-of-way.




Raymond Graham
 Raymond Graham
 R.P.E. 8409 L.S. 9978 Indiana
 3215 N. Smith Pike
 Bloomington, Indiana
 March 13, 1981

FILED
 APR 20 1981

V. Simpson
 Auditor Monroe County, Indiana

PLAT of SURVEY

NAGOSKY North Line
Section 9, T9N, R1W
D.R. 418, P. 99



REPORT of SURVEY - (Owner) Anne C. Nagosky (D.R. 488, P.99)
 (Clients) John P. and Roxana B. Nagosky

In accordance with Title 864, chapter 12 of the Indiana Administrative Code, a report of survey is required to explain procedures used in establishing the subject property lines and to provide an opinion regarding uncertainties in the boundary locations. At the request of the clients, the scope of this survey was limited to the North line of the 105 acre parcel recorded in Deed Record 488, page 99, Office of the Recorder of Monroe County, Indiana.

The North line of the subject Nagosky property adjoins the South line of the former Kenneth Stuart property. This line was surveyed by Bledsoe, Tapp, and Riggert in November 2003 prior to sale of the Stuart property to Laughlin and Millican and construction of an access road. The client furnished copies of surveys performed by Bledsoe, Tapp, and Riggert along with a design drawing for the proposed access road.

Our survey of the North line of Nagosky found seven Bledsoe / Tapp rebar monuments along the line indicated on our plat of survey as points 8, 13, 104, 106, 108, 109, and 110 from East to West. The position of these monuments checked within 0.25 feet or less variance from the positions shown on the plat of survey by Bledsoe / Tapp. Two of the angle points in this line (points 103 and 105) were not monumented by Bledsoe / Tapp with these positions calculated from the adjoining monument locations and the bearings and distances provided on the Bledsoe / Tapp survey plat.

Uncertainties in the boundary positions may result from any or all of the following factors:

A. Variances in reference monuments

1. The Bledsoe / Tapp survey set a rebar labeled as the West quarter corner of Section 9 (point 110) which was set at the midpoint between the Southwest and Northwest corners of Section 9. Point 110 was set 17 feet North of a 12" x 15" limestone fence corner post with a continuous fence running South and East from the stone post.

If the stone post would have been used as the West quarter corner of Section 9, the difference between the fence line and the half section line based on the Bledsoe / Tapp survey is 17 feet at the stone post location and 13.88 feet at the North / South jog in the line between points 106 and 108.

B. Ambiguity in record descriptions and plats

1. The Eastern most course of the North line of Nagosky is listed as "West, a little North, 49 1/2 rods (816.75 feet) with a fence". No record description could be found for the Stuart property which adjoins to the North.
2. The West course of the North line of Nagosky is listed as West along the half section line to the Northwest corner of the quarter section with no reference to a fence.

C. Inconsistencies in lines of occupation

1. Testimony from Bernard Guerretaz, land surveyor for Bledsoe, Tapp, and Riggert, indicated that the Eastern half of the North line of Nagosky (South line of Stuart) was established from the as-built fence location in the field. Their line has three courses with a 28 degree deflection angle at point 104. The record description has one course listed as "West, a little North 49 1/2 rods with a fence". Our survey did find a fence remnant to the East of the Bledsoe / Tapp rebar set at point 104, but did not find a continuous fence along the monumented line.
2. A continuous fence line was found on a fairly straight line between the tree location (point 103) and the rebar found at the fence corner (point 20). This fence is supported by a combination of tree trunks and fence posts. This fence is continuous except for the two sections that were removed during the construction of the new logging road.
3. John Nagosky verbally testified that the fence location at point 15 on the North side of the new logging road was the property line. Mr. Kevin Enright also verbally testified that the continuous fence line between points 103 and 20 was the property line. Mr. Enright stated that he boarded horses on this property for 18 years and frequently had to repair this fence.
4. The distance between the continuous fence line between points 103 and 20 and the Bledsoe / Tapp rebar set at the point 104 angle point is about 90 feet. The approximate area between these two lines is about 0.78 acres.
5. The new logging road extends South of the testified property line following the fence as much as 60 feet and extends South of the fence line for a length of about 700 feet.
6. The new logging road also encroaches onto the Nagosky property at the jog and is entirely South of the rebar found at point 108.

7. The gravel access road encroaches over the property line as staked by Bledsoe / Tapp between points 108 and 109. This encroachment is as much as 8 feet where the road crosses the valley. The gravel road is entirely North of the old fence line to the East of the stone fence corner.
8. The fence along the East property line is as much as 30 feet West of the monumented North to South line. Both King and Nagosky are aware that the fence is West of the theoretical line in this area.

D. Theoretical Uncertainty

Due to random errors caused by survey instrument precision and survey field methods used, the theoretical uncertainty of all points in our survey is 0.25 feet. This means that the actual location of all points is within this uncertain distance from the point locations based on the survey plat bearings and distances.

CERTIFICATION


I, Kevin B. Potter, L.S. # S 0487, hereby certify that the attached plat represents a recent survey performed in accordance with survey standards set forth in Title 864, chapter 12, of the Indiana Administrative Code and in witness thereof I hereunto attach my hand and seal this

17TH day of JULY, 2004.

Kevin B. Potter

Kevin B. Potter, L.S. # S 0487
 369 East Cunningham Street
 Martinsville, Indiana 46151


100 0 100 200



Oct 2^d A D 1849

Layed off 2 acres for a mill lot for Nicholas Flermer
 & Daniel Thomas at Bean Blossom Bridge on the Morgantown
 road in Section 35 T⁴⁰ R 1. East Fixed for a starting point
 the N E cor having for witness trees a Sycamore 8 inches
 diameter S 27° E 2 chain & 38 links dist Elm 16 inch diam
 S 22° W 1 chain & 46 links distant ran from said corner
 S 41° W 20 poles then N 41° W 16 poles then N 41° E 20 poles
 then to the starting point
 variation 6° degrees

James Woodburn M. C. S.

Feb 16th 1850

Surveyed for James Small the following Tract of land in
 Section 15 T⁸ R 2 west in the Nth q^r of said Section
 Beginning at (A) the S E cor of said q^r running North
 106 poles to (B) From (D) the Sth cor of said quarter
 N 106 poles to (C) then from C to B across said q^r
 Established corners at C & B

Witness trees at C Sugar 15 inch diam
 N 36° W 10 1/2 links distant Beech 18 inch diam N 42° E
 43 links dist

at B Black Oak 3 inch diam S 25° W
 23 links distant Hickory 18 inch diam N 35° W 60 1/2 links dist

James Small & Hugh Sample
 chain Bearers

James Woodburn, M. C. S.

March 2^d 1850

Surveyed as Dower to Mary W. Hughes & her husband
 James Hughes thirteen & 5/6 acres in the Nth corner of
 of the Sth q^r of Nth q^r of Section 9 T⁹ R 1. west
 Established the Nth & N E cor with ss trees of the Nth
 cor Beech 12 inch diam N 15° W 5 links dist " 16 inch diam
 S 25° E 32 links dist N E cor Beech 12 inch diam S 47 1/2° E
 9 links dist Poplar 8 inch diam N 87° W 20 links dist
 Said Dower was layed off in a Square each side being 47.04
 Poles Variation 5°

John James D. Robertson &
 Joseph Bangs chain Bearers Sworn

James Woodburn M. C. S.

thens S 82 1/2° W 79 poles & 6 lbs to R witness Beach 15 inches in diam
 N 5 1/2° W 12 lbs dist Beach 18 inches in diam S 18° W 15 1/2 lbs dist thens S 82 1/2° W
 39 poles 15 1/2 lbs to S witness R Oak 5 inches in diam S 83° W 7 lbs dist
 R Oak 4 inches in diam N 50° E 21 lbs dist then commenced at the
 N E corner Ran S 82 1/2° W 79 poles & 12 lbs to T witness Beach
 15 inches in diam S 87° W 18 lbs dist Beach 18 inches in diam East 5 1/2 lbs
 Chancery Barers J. W. Parkman John Logan & William Robertson sworn

John Logan \$150 paid
 for Samuel Getty 3.50 paid J. S. Buskirk M. C. S
 Samuel Rand 1.50 paid
 Alexander Robertson 1.50 paid
 William Robertson 1.00 paid
 David Hunter 1.00 paid
 Sarah Romans 1.00 paid
 John Mosure 1.00 paid
 James Flash 1.00 paid

May the 15th 1861

Ran the following lines & made the following corners in
 Section 9. T. 9. R. 1. W. for John Stuffle commenced
 at the N. E. corner old witness gone new ones made
 Beach 8 inches in diam N 70° W 8 lbs dist
 Do 10 ... S 15° W 25 ...
 thens S 5° E 160 poles & 7 lbs to the Eastern 1/2 mile post
 thens S 85° W 160 poles & 12 lbs to the center of said Section
 witness Hack Berry 10 inches in diam N 35° W 63 lbs dist
 Hack Berry 8 ... S 67° E 90 ...
 Chancery Barers } John Stuffle } sworn
 } Jacob Stuffle }
 fee \$3.00 paid

J. S. Buskirk M. C. S

State of Indiana }
 County of Monroe } S. S.

Monroe Common Pleas Court We the Commissioners
 Appointed by said Court at April Term 1861 to make
 Partition of the Real Estate of belonging to Lawson
 Oliphant and Others Heirs of Thomas Oliphant Sen^r late
 of said County and State Dec^d after being duly sworn as
 will appear by an Oath administered on the Warrant of Partition
 delivered to us and here with returned and filed we

continue from day to day until completed
Feb 14th 77

Joseph Adams

Copied from the Republican Progress a newspaper published in
Bloomington Monroe County Ind said notice having been published
three successive weeks in said paper

M. H. Buskirk M. C. S.

The following chairman and flagman were sworn during
the survey by consent of parties

James Sisco

Isaac J. Wampler

John Adams


Wilford Adams

Chain

bearers sworn

Stephen Deckard } flagman
I. M. Knight } sworn

M. H. Buskirk M. C. S.



Survey of Sections 16 & 17 & 13
R 1 W March 12th 13th & 14th
1877

For John Blair, Thomas Blair
Ben Owens, John Parks
Albert ~~Parks~~ Dan Stout

Commenced at S $\frac{1}{2}$ m p 17 and ran S 86° E 161 Poles 12 $\frac{1}{2}$ lks to S. E.
Section corner Thence S 86° E 160 Poles 6 $\frac{3}{4}$ lks. to the S $\frac{1}{2}$ m p of section 14
T. 9. R. 1. W. corrected back and set corner. limestone (A) witness Black walnut
13 $\frac{1}{2}$ S 73° E 32 $\frac{1}{2}$ lks. Elm 27 N 32° E 49 $\frac{1}{2}$. From Thence N 4° W 160 P 4 lks to corner
heretofore established. Then commenced at S $\frac{1}{2}$ m p section 14 ran N 4° W
317 Poles 19 $\frac{1}{2}$ lks to N $\frac{1}{2}$ m p heretofore established. Then commenced at S E
corner of section 17 T. 9. R. 1. W. and ran N 4° W 117 P 22 lks to E $\frac{1}{2}$ on p
found one of the original witness trees still standing. Thence S 86° W 321 Poles
16 lks to western $\frac{1}{2}$ m p heretofore established drove stake in the center
of the section of 17 where the two lines running from East to west $\frac{1}{2}$ on p and
from North to South $\frac{1}{2}$ on post cross. Then commenced at S W corner of 17 and
ran S 86° E 161 Poles 17 lks to S $\frac{1}{2}$ m p of the same established corners
in the above survey as per plat above and field notes below

- B Stone heretofore set original witnesses much decayed and new ones made (S E cor p 17)
Black walnut 1 N 53° W 28 $\frac{1}{2}$ lks Red oak 1 S 41° W 6
- C Eastern $\frac{1}{2}$ m p 17 set limestone marked with +
witness Black Walnut 10 S 95° E 141 $\frac{1}{2}$ lks Burdock 30 S 31° W 8 lks

- D Corner 120 Poles east of center of section limestone mark with +
 Witness Beech 12 S 77° W 180 lks Ash 4 N 79½ E 144½ lks
- E Corner established 120 Poles E of S ½ on p. sec 17 limestone marked with +
 Witness poplar 7 N 21° E 41½ poplar 6 S 85½ E 91½ lks
- F Established corner for John Blair and Ben Owens 83 Poles 4¼ lks south of corner
 120 Poles East of S ½ on p. of 17 limestone marked with +
 Witness Beech 20 N 20° E 15 Sugar 12 S 6° W 46½
- G Established corner for John Parkes and Dan Stout 53 Poles 8½ lks N of corner
 120 poles East of S ½ on p. of 17, came right in the branch impossible to make a
 corner stone stand set a sand stone 2 Poles west of true corner. +
 witness to said stone Beech 18 N 82 W 16¼ lks Beech 22 S 74 E 77 lks
- H Stone set at 80 Poles E of W ½ on p. 16, 9, 1, W marked with +
 new witness Elm 34 S 70 E 20
- I Established corner at S ½ on p. set stone marked with a +
 witness Beech 18 S 70 E 64 lks Black walnut 12 N 46½ W 61 lks
- J Set limestone witness Beech 14 S 54° W 22 lks Beech 12 S 34 E 28½ lks
- K Established corner 53 Poles 8½ lks N of S ½ on p. of section 17
 Stone set witness Elm 34 N 22 W 61 Black walnut 3 S 47½ W 28½ lks
- + Robert Patton } chain bearer } John W Baugh
 Jacob Patton } sworn } flagman sworn

The above survey was done in accordance with the following notice which was served on the parties named 10 days before the day the survey commenced

Notice is hereby given to Daniel Stout and John Parkes that we will proceed together with the county surveyor or his deputy on the 12th day of March 1877 to relocate and perpetuate all the lines and corners necessary to established in Sections 16 & 17 T 9 N R 1 W commencing at the Southern ½ mile post of Section 17 Town and range aforesaid at 10 o'clock A.M. of said day you are requested to be there at said time and place else the survey will proceed in your absence

John Blair
 R I Owens

Mc Hc Bustin to Surveyor of Monroe Co

+ Sept 21st 1885 Commenced at The S. E. corner of Section 29
 T. 9, R. 1, W. Ran S 87° W 323 Poles 9 lks and hit corner corrected
 back and established corner 40 Poles 11 lks East of S W cor
~~at Walnut 52 in~~ N 63° E 30 lks N. Walnut 15 Hickory, N 33° W
 25½ lks Thence N 87° W 162 Poles 5 lks and established corner
 40 Poles 10 lks east of W ½ on p witness Oak 36 in S 4°
 W 23 lks N Walnut 13 in N 32½ W 107½ lks also established
 corner at half dirt bet W ½ on p and center witness Oak 30
 S 25° E 24 lks Oak 28 S 11° W 81 lks The above Survey was made
 at the request of parties interested (George Thornton and Wm Alexander)
 Wm Stewart { chairman
 Sam Brown { sworn
 Stephen White flagman sworn.

M H Buehler M. C. S.

+ Thursday the 22nd day of October 1885 Comes now
 The following named parties resident land holders of
 Section 9 Town 9 Range one west namely Joseph Payne,
 James Rogers, Frank Whisenand, Doctor R. Wiley, and
 William Dunnihoo, and by agreement asks the following
 Survey in said Section Whereupon we proceeded to do
 the same with the assistance of George W. Whisenand
 Hugh Atkinson and Doctor R. Wiley as chain carriers
 and Frank Whisenand and William Johnson as
 flagman all of whom were duly sworn
 Established W ½ on p witness Black walnut 4 inches
 N 24° E 61½ lks Jack oak 6 inches N 83° E 128½ lks
 Center of Section new witness to old corner Sycamore 5
 inches S 42° E 14½ lks made new witness at N. E. corner
 White Oak 12 S 45° E 48 lks
 I hereby certify the foregoing to be a true report
 of the Survey by me made given
 under my hand this Nov 30th 1885.

George B. Rader
 Sept S., M., C.

Bowman & Wylie Survey Section 9 T 9 R 1 W

Nov 5th 1895 Surveyed the following lines in section 9 T 9 R 1 W commenced at corner theretofore established in the center of said Section reestablished or rather perpetuated this corner by making new witnesses Elm 8 S 78° W $7\frac{1}{2}$ lks Elm N 62° E $6\frac{1}{2}$ lks Ran north 139 Poles 22 $\frac{1}{2}$ lks ran 7 lks west of corner at $\frac{1}{2}$ m p. corrected back and drove stake at average in said line Thence West 110 Poles 14 lks to west side of section landing 80 Poles 17 lks south of the N E corner of section 9. moved stake 17 lks north and corrected line back east from it to find the line between Doctor R Wylie and Peter Bowman they each being present and agreeing to the same

Thomas Whisenand } chainmen
D. R. Wylie } sworn

Lewis Goodwin } flagman sworn



The above survey was made in compliance with the following Notice of Survey

Notice is hereby given to Frank Whisenand Mrs Johnson D. R. Wylie & wife that I will proceed together with the county surveyor of Monroe county Ind or his deputy on the 5th day of November 1895 to run all the lines that may be necessary to locate the line between my land and the land of D. R. Wylie & wife in section 9 Town 9 R 1 W. Meet at the residence of D. R. Wylie at 10 o'clock A. M. on said day Be present at said time and place else the Survey will proceed in your absence
This Oct 26th 1895

Peter Bowman

This notice was returned to me by Peter Bowman with the following endorsement by him made
Mrs Johnson was notified by copy
D. R. Wylie & wife " " "
Frank Whisenand was notified by reading
10 days before commencing survey

M. H. Brunkirk
Sept 11 C & S

[illegible]

Bledsoe Tapp & Riggert, Inc.
-Quality Land Surveying and Civil Engineering Services-

1351 West Tapp Road
Bloomington, IN 47403
(812) 336-8277
FAX (812) 336-0817

1324 "K" Steer, Room 150
Bedford, IN 47421
(812) 275-0001
FAX (812) 275-8251

STUART BOUNDARY
PROPERTY
FOR
KENNETH STUART

DESIGNED BY : B.G.
DRAWN BY : *D.L. Sinters Jr.*
CHECKED BY : B.E.B.
DATE: NOVEMBER 17, 2003

SECTION BREAKDOWN

SHEET

1 OF **5**

PROJECT NO. **4457**